Accessories, to be ordered separately



IH-A 24630, IH 42630
Insulating hood, of flexible rubber with outer conductive layer and a preinstalled insulating rod. To be mounted on the bushing in a switchgear or a transformer 630 A to insulate it when a cable is temporarily disconnected but other cables are energized.



IP 630
Screened insulating plug for installation in the connector so that the cable can be energized even when disconnected from the switchgear or transformer 630 A.



PC 630/250
Parallel coupling piece. Replaces the plug in CSE-A 630 A when making a parallel connection to CSE-A 250 A. Delivered in 3-phase kits and hex bit socket.



PSSK
Screen separation kit to achieve a metallic screen on each core for 3-core cable.



TSH
Branch seal kit to achieve a sealing on each core for 3-core cable.



MA-A 630
Measurement adapter used for mega ohm Ω measurements and to perform different measurements up to 5 kV DC, for example determination of phases, 630 A.



CSAP-A
Surge arrestor, 630 A.



PG 630
Bushing for voltage testing.



PG-A 630
Bushing for voltage testing, 36 – 42 kV.



CSEP-A
Parallel cable connector.



JPB 630
Universal earthing device with two fields of application for 630 A and 12-42 kV:

- As earthing-for-work device mounted at the back of a connected cable connector CSE-A for 630 A.
- As short-circuit protective earthing mounted in front of a disconnected cable connector CSE-A for 630 A.



JPA V
Tool for earthing device, JPB 630.

Designation	Description	Qty. per kit	Weight kg/kit	See page
IH-A 24630	Insulating hood, 12 – 24 kV, 630 A	3	5.2	33
IH-A 42630	Insulating hood, 36-42 kV, 630 A	3	5.5	33
IP 630	Screened insulating plug, 630 A	1	2.2	33
PC 630 / 250	Parallel coupling piece	3	3.0	33
PSSK	Screen separation kit, heat-shrink for 3-core cable	1	1.0–1.1	54
TSH	Branch seal	1	0.3–1.0	55
MA-A 630	Measurement adapter, 630 A	3	0.2	33
CSAP-A	Surge arrestor, 630 A, 12 – 24 kV	1	3.6–5.0	35
PG 630	Bushing for voltage testing, 630 A, 12 – 24 kV	1	1.5	33
PG-A 630	Bushing for voltage testing, 630 A, 36 – 42 kV	1	2.0	33
CSEP-A	Parallel cable connector	1	5.7–9.8	34
JPB 630	Earthing device, 630 A	1	5.0	33
JPA V	Tool for earthing-for-work device, JPB 630	1	1.8	33